



GREKKON LIMITED

Irrigating Your Farm To Life

| Hakimi Building KSM Rd, Next to Eldoret National Polytechnic | P.O. BOX 2023,
00606 Nairobi |
| Tel +254 711 895 635 | sales@grekkon.co.ke / grekkon.co.ke

QUOTATION

Moses	
Tel 12345678	
Nairobi	
2022	

Project details: Borehole mud drilling to 160M bgl by 8' diameter, constructed with 6' diameter multi-steel casing casing, and gravel packed. Tail end services being test pumping and complete water chemical testing.

	ITEM DESCRIPTION	UOM	QTY	@	AMOUNT
1. MOBILISATION					

2. DRILLING

2.1	Drill an 8' bore from 1-120M	M	100		
2.2	Ditto above but from 120-160M	M	60		
2.3	Allow for collection and sampling of drill cuttings at 2M intervals	Ls	1		
SUB TOTAL DRILLING					0

3. WELL CONSTRUCTION

3.1	Supply and install multi-steel casing	Set	1		
3.2	Supply and install multi-steel slotted casing	set	1		
3.3	Supply and install gravel pack with average grain size of 2mm	Ton	10		

3.4	Grouting of top 3 meters of annular space between casing and borehole	Sum	1		
3.5	Supply of drilling components such as form, bentonite and other sundries	Set	1		
3.6	Form concrete surface plug around casing with dimensions 1,000x1,000x1,000mm	Sum	1		
3.7	Supply and install steel surface casing	Sum	1		
SUB TOTAL WELL CONSTRUCTION					0

4. WELL DEVELOPMENT AND TESTING

4.1	Well development using air or water jetting as recommended by the hydrogeologist	Hr	12		
4.2	Insertion and removal of equipment	Hr	12		
4.3	Supply and install 203mm well cap	Sum	1		
SUB TOTAL WELL DEVELOPMENT AND TESTING					0

5. TEST PUMPING & CHEMICAL WATER ANALYSIS

5.1	Test pumping	Hr	24		
5.2	Chemical analysis of water	Sum	1		
SUB TOTAL TEST PUMPING & CHEMICAL WATER ANALYSIS					0

Note:

1. Quotation includes: Drilling, Casing, Test Pumping and Water Analysys.